CAPCO

QS SPECIFICATIONS

EXPOSED TEE SUSPENDED CEILINGS

Duraceil – 600 x 600 x 6mm Vinyl clad Calcium Silicate Tiles

Supply and install 600 x 600 x 6mm Duraceil Ripple White vinyl clad calcium silicate aluminium foil backed ceiling tiles laid onto CKM T38/24W pre-painted white exposed tee grid system. Main tees suspended by means of 19 x 0,5mm GMS strap hangers at 1,200m centres with 4,2 x 13mm wafer-tek screws to tees and 6 x 40mm express nails and M6 washers to slab. All in accordance with CAPCO and SABISA installation instructions.

Duraceil – 1200 x 600 x 6mm Vinyl clad Calcium Silicate Tiles

Supply and install 1200 x 600 x 6mm Duraceil Ripple White vinyl clad calcium silicate aluminium foil backed ceiling tiles thick laid onto CKM T38/24W pre-painted white exposed tee grid system. Main tees suspended by means of 19 x 0,5mm GMS strap hangers at 1,200m centres with 4,2 x 13mm wafer-tek screws to tees and 6 x 40mm express nails and M6 washers to slab. All in accordance with CAPCO and SABISA installation instructions.