

TITLE : Report on the Large-scale Fire Resistance

properties of the Capco 60 minutes Fire

Rated Ceiling (Insulated)

REQUESTED BY : Capco (Pty) Ltd

PO Box 4203

Riverhorse Valley East

DURBAN

4017

CONTRACT No : FTC 23/212 (a)

ISSUE No : 1

DATE : 01 December 2023

SCOPE

This report classifies the Fire Resistance Properties of the **60 minutes Fire Rated Ceiling (Insulated)** when tested and classified in accordance with the **SANS 10177 – 2** test protocol.

Section 1: Detailed information on the specimen construction

Section 2: Test protocol used for classification

<u>Section 3:</u> Observations made, temperatures recorded with photographs taken before, during and after the test

Section 4: Discussion of results

Section 5: Conclusion

Annexure "A": Company information

Annexures "B": System information and detailed drawings supplied by Capco



TABLE OF CONTENTS

	LIST OF FIGURES AND TABLES	1
1.	SPECIMEN DESCRIPTION	2
2.	FIRE RESISTANCE: SANS 10177 - PART 2:2005	4
2.1.	TEST PROCEDURE	4
2.2.	TEST EQUIPMENT	4
3.	TEST RESULTS	5
4.	DISCUSSION OF RESULTS	.12
5.	CONCLUSION	.13
	ANNEXURE "A"	.14
	ANNEXURE "B"	.15

LIST OF FIGURES AND TABLES

Figure	1.1:	The Capco (Insulated) Ceiling with thermocouples on the unexposed side prior to tes	ting
			3
Figure	1.2:	The Capco (Insulated) Ceiling from the exposed side	3
Table	3.1:	Observations recorded during the SANS 10177 – 2 test	5
Figure	3.1:	Furnace temperatures recorded during the large-scale FR test	6
Figure	3.2:	Temperatures recorded on the surface of the specimen	7
Figure	3.3:	First layer of boards sagging	8
Figure	3.4:	Smoke release density increase	8
Figure	3.5:	Insulation darkening on joint	9
Figure	3.6:	Significant smoke release near TC 1	9
Figure	3.7:	First layer of boards sagging significantly	.10
Figure	3.8:	Glowing observed through insulation	.10
Figure	3.9:	System collapsed near back perimeter	.11



SPECIMEN DESCRIPTION 1.

Capco installed the 60 minutes Fire Rated Ceiling (Insulated) into FIRELAB's Horizontal SANS 10177 - 2 test facility.

Description of the ceiling system:

Capco 60 minute Fire Rated Ceiling System:

System Abbr. name: Capco (Insulated) Ceiling

Total Thickness: ± 68 mm

Proposed Application: Ceiling system

Application requirement: FR 60 Load required: N/A

System make up:

Board: 15 mm Fire Shield Board

Plaster: Casofour/Capco Jointing compound

Length (per board): 3.0 m Width (per board): 1.2 m **Total Thickness** 30 mm

System Composition:

Laver 1: Insulation – Capco Ultrasonic Batt 47.5 kgs/m³

Grid 1: T38/35G Tee Grid System

15 mm Fire Shield Drywall screwed to grid. Taped and jointed Layer 2: Layer 3: 15 mm Fire Shield staggered with 100 x 0.5 mm galvanised

steel sheet strips at joints

Support:

Main T's: Capco Delta T38/35G Main Tee (3.600 m) + Cross Tees

(1200 mm)

Hangers: 25 x 25 x 0.5 mm galvanised M/S angles

Clips: N/A

The test specimen is shown from the exposed and unexposed sides in Figures 1.1 and 1.2 prior to commencement of the test.





Figure 1.1: The Capco (Insulated) Ceiling with thermocouples on the unexposed side prior to testing



Figure 1.2: The Capco (Insulated) Ceiling from the exposed side



FIRE RESISTANCE: SANS 10177 – PART 2:2005

2.1. TEST PROCEDURE

The nominal 3 meter wide by 6-meter long system (3 meter section with insulation and the remaining 3 meter without insulation) was tested for fire resistance in **FIRELAB**'s large-scale air-aspirated diesel furnace. The furnace temperature was controlled to follow the **ISO standard time-temperature curve** as stipulated in **SANS 10177 – 2**. The **Fire Resistance Rating (FRR)** of the system is determined based on the following criteria:

- Stability (R): The system may not collapse or fail structurally during the test.
- * Integrity (E): The system is deemed to have failed should flames be observed on the unexposed side or an opening larger than 6 mm wide or 150 mm long is noted.
- Insulation (I): The temperature on the unexposed surface may not exceed 140 °C plus ambient temperature on average or 180 °C plus ambient maximum at any of the measured surface positions.

The **Stability** and **Integrity** criteria are evaluated through observations which are noted in Table 3.1.

Insulation was measured using 5 thermocouples (TC 1 - TC 5) placed in a grid of equal area onto the surface of the specimen.

The insulated ceiling was tested simultaneously with the uninsulated ceiling.

2.2. TEST EQUIPMENT

- Data logging equipment c/w controller
- Stopwatch
- Type K thermocouples
- SANS 10177 2 Horizontal Test Facility



3. TEST RESULTS

Capco - Capco Ceiling

OBSERVATIONS DURING THE SANS 10177 - 2 TEST

TIME (hh:mm:ss)	DESCRIPTION
00:00:00	- Test Started -
00:02:02	Light smoke release on left perimeter
00:04:50	Light smoke release on front perimeter
00:10:06	General smoke release increase
00:18:40	Smoke coming through insulation in the middle
00:19:20	First layer of boards starting to sag
00:36:00	Density of the smoke released increased
00:41:00	Pieces flaking off the first layer of boards
00:52:40	Insulation darkening on joint
00:55:20	Significant smoke release near TC 1
00:56:00	Board joints starting to open (exposed side)
00:59:00	Board charring on right perimeter and edging buckling (uninsulated section)
01:00:00	First layer of boards sagging significantly (insulated section)
01:03:20	System sagging near back perimeter and glowing under insulation (insulated section)
01:07:00	Insulation sagging significantly at back perimeter (insulated section)
01:09:55	System collapsed near back perimeter (insulated section) » Fails Stability
01:10:00	- Test Concluded -

Note(s): Tested on 26/10/2023, ambient temperature during the test = 28.5 °C

The observations above are for both the insulated ceiling and the uninsulated ceiling

Table 3.1: Observations recorded during the SANS 10177 – 2 test






Figure 3.1: Furnace temperatures recorded during the large-scale FR test






Figure 3.2: Temperatures recorded on the surface of the specimen






Figure 3.3: First layer of boards sagging



Figure 3.4: Smoke release density increase





Figure 3.5: Insulation darkening on joint



Figure 3.6: Significant smoke release near TC 1





Figure 3.7: First layer of boards sagging significantly



Figure 3.8: Glowing observed through insulation





Figure 3.9: System collapsed near back perimeter



4. DISCUSSION OF RESULTS

Results in terms of **SANS 10177 – 2**: Ceiling system with insulation

Stability (R): The specimen collapsed after 60 minutes.

Stability satisfied for 60 minutes

Integrity (E): The specimen collapsed after 60 minutes.

Integrity satisfied for 60 minutes

* Insulation (I): None of the thermocouples reached their maximum allowable

temperatures during the test duration.

Insulation satisfied for 60 minutes

20 November 2023



5. CONCLUSION

The Capco 60 minutes Fire Rated Ceiling (Insulated) was tested for Fire Resistance in accordance with the SANS 10177 – 2 test protocol and is classified as follows:

SANS 10177 - 2 » FR60

🤲 Stability (R) 🌖 60 minutes

Integrity (E) » 60 minutes

🦊 Insulation (I) 🎐 60 minutes

Compiled by: T.H. Swart

Approved by: J.S. Strydom

This copy has been produced from a .pdf format electronic file that has been provided by **FIRELAB** to the sponsor of the report and may only be reproduced in full. Extracts or abridgments of reports must not be published without permission of **FIRELAB**. The original signed paper version of this report is the sole authentic version. Only original paper versions of this report bear authentic signatures of the responsible **FIRELAB** staff.



ANNEXURE "A"

– Compan	y Information –	FIRELAB			
Company Name:	Capco (Pty) Ltd				
Company Trading Name:	CAPCO				
Company Registration Nr.:	2019/574495/07				
Company VAT Nr.:	4600104667				
Core Business Activities:	Distributor and stockist to Ceiling ar	nd Partition Industry			
Postal Address:	P.O Box 4203, Riverhorse Valley E	ast, Durban, 4017			
Physical Address:	2 Corobrik Place, Riverhorse Valley	Business Estate, Durban, 4017			
Company contact number:	031 569 6090				
Direct Contact Details					
Technical (name):	Barry Gould - Managing Director				
Cell phone number:	083 272 1871				
Email address:	barry@capco.co.za				
Financial (name):	Justin Ellis - Finance Manager				
Cell phone number:	083 856 6447				
Email address:	justin@capco.co.za				
– Test & Sample Information –					
Test Required:	60 minutes Fire Rated Ceiling				
Sample/Product name:	Capco FireShield Gypsum Ceiling				
Intended Use:	Residential / Commercial / Industrial Building				
Sample/Product Description: (Short description of sample or product submitted for testing, and type of material to be tested)		frame / structural steel or timber beams of 15mm Fire resistant gypsum boards			



ANNEXURE "B"

SANS 10177 Part 2 –Ceiling Specimen Description –



ceimig spe	centrem bescription	
eiling system description	•	
System name:	Capco 60minute Fire Rated Ceiling	
System type:	Capco FireShield Gypsum Board	
Proposed Usage:	Residential between garage and loft over: 30minutes a minutes required	and Commercial: 60
stem make up:		
Board:	15mm FireShield board	
Plaster:	Casofour / Capco Jointing compound	
Length (per board):	3,000m	
Width (per board):	1,200m	
Overall Thickness:	15mm x 2 = 30mm + T38/35G grid	
oduct composition (inclu	udes skin coat & coating):	
Layer 1:	15mm FireShield Drywall screwed to grid. Taped and jo	ointed
Layer 2:	15mm Fireshield staggered with 100 x 0,5mm galvanis at joints	ed steel sheet strips
Layer 3:	N/A	
Layer 4:	N/A	
Layer 5:	N/A	
pport:		
T's:	Capco Delta T38/35G Main Tee (3,600m) + Cross tees	(1200mm)
Hangers:	25 x 25 x 0,5mm galvanised M/S angles	
Clips:	N/A	



Capco: One Hour Fire-rated Gypsum Ceiling. 60 Minute Fire-rated ceiling description.

- 1. Ceiling suspended from light steel frame, structural steel frame or structural timber beams with 25 x 25 x 0,6mm galvanised mild steel angle hangers fixed at 750mm centres to Capco Delta galvanised mild steel covered tee system T38/35G fire rated main tees with Wafer Tek screws. Main tees supported at perimeter walls on Capco C39/25 Bulkhead "C" Channels fixed at 400mm centres. Delta 1,200m Cross tees T38/35G slotted into main tees at 300mm centres. Capco 15mm thick FireShield fire resistant gypsum board fixed to Covered Tee system with 25mm Drywall screws at 150mm centres and joints taped with 50mm wide fibreglass mesh tape and jointed with Capco jointing compound. All screw heads to be stopped with joint compound. Second layer of Capco 15mm thick FireShield gypsum board fixed in staggered pattern through first layer of board with 45mm drywall screws into covered tee grid system including 100 x 0,5mm galvanised mild steel strips behind all second layer board joints. Gypsum board Tapered edge joints to be fitted with 50mm fibreglass tape and flush jointed with Capco jointing compound. All screw heads to be stopped with Capco jointing compound.
- 2. Alternate. All as above with 50mm thick by 80Kgs/m³ density Capco mineral wool blanket 1,200m wide laid over entire suspended ceiling with joints closely butt jointed.



Page 17 of 22

