## **CAPCO**

## **QS SPECIFICATIONS**

## FLUSH PLASTERED CONCEALED TEE SUSPENDED CEILINGS

## CAPCO 9mm Plasterboard Tapered Edge & T38/35G Galvanised Concealed Tee Grid System

Supply and install CAPCO 3,600m T38/35G main tees at 1,200m centres in one direction and CAPCO 1,200m T38/35G cross tees at 400mm centres perpendicular to main tees. Main tees to be suspended at 1,200m centres by means of 25 x 25 x 0,6mm GMS angle hangers fixed to bulb of main tee with 4,2 x 13mm wafer-tek screws and to slab with 6 x 40mm express nails and M6 washers. Fit 9mm thick CAPCO standard gypsum tapered edge board to underside of grid system with tapered edge of board facing down with 25mm drywall screws at 150mm centres. Cover all drywall screw heads with CAPCO Jointing Compound. Apply 50mm wide self-adhesive glass fibre tape to all joints and finish with CAPCO Jointing Compound. Installation to be in accordance with Capco and SABISA installation instructions.

Option: Flush plaster entire ceiling with 3-4mm RhinoLite Skimming Plaster.