CAPCO

QS SPECIFICATIONS

EXPOSED TEE & PLASTERBOARD GALVANISED CONCEALED TEE SUSPENDED CEILINGS

SIGMA Ceiling Transition 15

Supply and fit SIGMA Ceiling Transition 15 satin white epoxy coated aluminium Shadowline trim between same level gypsum flush plastered ceiling and exposed tee suspended ceiling. Ceiling transition to be suspended from RC slab at 1,200m centres by means of 25 x 25 x 0,6mm GMS angle fixed with 6 x 40mm express nails and M6 washers to slab and 4,2 x 13mm wafer-tek screws to ceiling transition.

SIGMA Ceiling Transition 20

Supply and fit SIGMA Ceiling Transition 20 satin white epoxy coated aluminium Shadowline trim between same level gypsum flush plastered ceiling and exposed tee suspended ceiling. Ceiling transition to be suspended from RC slab at 1,200m centres by means of 25 x 25 x 0,6mm GMS angle fixed with 6 x 40mm express nails and M6 washers to slab and 4,2 x 13mm wafer-tek screws to ceiling transition.

SIGMA Transition 30 with Led Light

Supply and fit SIGMA Ceiling Transition 30 with LED Light satin white epoxy coated aluminium Shadowline trim between same level gypsum flush plastered ceiling and exposed tee suspended ceiling. Ceiling transition to be suspended from RC slab at 1,200m centres by means of 25 x 25 x 0,6mm GMS angle fixed with 6 x 40mm express nails and M6 washers to slab and 4,2 x 13mm wafer-tek screws to ceiling transition. Clip-in “U” shaped opaque diffuser into ceiling transition. Fit appropriate LED to ceiling transition (by others).

Option: Ceiling Transition 30 can be terminated anywhere. Fit end caps at termination points.

Option: Continuous squares or rectangles can be formed my mitring ceiling transition 30 section and fitting 50 x 50 x 30 x 3mm brackets to internal and external corners into recesses and securing with 2 No. 6mm cap screws.